


*Watertown Elementary Schools Building Project*

# DesignWatertown



**WPS Building Committee**

**Ai3 Architects, LLC**  
**Hill International, Inc**

August 21, 2019

Schools Project Website: [www.watertownschooldesign.com](http://www.watertownschooldesign.com)

*Watertown Elementary Schools Building Project*

# **SiteReview**







Site Review

# Site Organization: Watertown Elementary Schools


## Hosmer









## Cunniff



## Lowell



-  OUTDOOR PLAY SPACE
-  OUTDOOR LEARNING AREA
-  SCHOOL GARDEN
-  PEDESTRIAN CIRCULATION
-  OPEN PLAY SPACE
-  DISMISSAL AREA



# Site Furniture



Watertown Building Committee Presentation



# Garden Equipment



ten year warranty

twist-locking post-resistant lid

conical shape for easy removal

side ventilation




four screw pegs to secure composter to the ground

locking harvest door

Watertown Building Committee Presentation



# Hosmer: PreK-K Playground




Watertown Building Committee Presentation





# Hosmer: 1st-5th Playground






Watertown Building Committee Presentation





# Cunniff: K-1st Playground




Watertown Building Committee Presentation







# Cunniff: 2nd-5th Playground



Watertown Building Committee Presentation



# Lowell: Kindergarten Playground



Watertown Building Committee Presentation





# Hosmer


Existing Site






Site Review

# Proposed Grading 8/21: Hosmer Elementary School



Revised grading at field edge




Includes grading at bioswales



Site Review

# Existing Utilities: Hosmer Elementary School



### Legend


- Drainage Line ————
- Sanitary Line ————
- Water Line ————
- Gas Line ————
- Electric Line ————




Site Review

# Service Access: Hosmer Elementary School


A) Typical  
Delivery Truck




B) Typical  
Garbage Truck



C) WB50 Truck -  
Straight Approach




D) WB50 Truck -  
with Turnaround





Site Review

# Service Access: Hosmer Elementary School




Reduced planting heights





Site Review


**Service Access:  
Hosmer Elementary School**





Site Review

# Service Access: Hosmer Elementary School




Reduced planting heights





Site Review

# Service Access: Hosmer Elementary School



Reduced planting/fence heights





# Cunniff

Existing Site



Cunniff  
School  
Playground

Cunniff  
Elementary School

Chapman St

Chapman St

Chapman St

Warren St

Warren St

Warren St


Warren St



Site Review


# Existing Utilities: Cunniff Elementary School

- Legend
- Drainage Line ————
  - Sanitary Line ————
  - Water Line ————
  - Gas Line ————
  - Electric Line ————







**Service Access:  
Cunniff Elementary School**



A) Typical Delivery Truck



B) Typical Garbage Truck




C) Garbage Truck with Turnaround



# Lowell


Existing Site





Site Review

# Existing Utilities: Lowell Elementary School




### Legend

- Drainage Line 
- Sanitary Line 
- Water Line 
- Gas Line 
- Electric Line 



Site Review

**Service Access:  
Lowell Elementary School**




A) Typical  
Delivery Truck



Site Review


# Garden Landscape: Lowell Elementary School





Site Review


# Garden Landscape: Lowell Elementary School





*Watertown Elementary Schools Building Project*

# **Design**Progress





## Hazardous Materials Investigations: Results

### Services Conducted:

- Asbestos Containing Materials (ACM) inspection & [representative] sampling
- Polychlorinated Biphenyls (PCB's)
  - Electrical Equipment and Light Fixtures inspection
  - Caulking inspection
- Lead Based Paint (LBP) inspection

### Hosmer

#### Asbestos Containing Materials (ACM)

- 159 samples tested, 27 contain asbestos
- ACM in good condition does not present a health issue unless it is disturbed; not necessary to remediate

#### Polychlorinated Biphenyls (PCBs)

- 0 PCBs were found
- Tubes in light fixtures, thermostats, signs and switches were assumed to contain mercury; should be disposed in an EPA approved landfill
- Caulking was assumed to contain PCBs; EPA requires that all be disposed if level exceeds 50 mg/kg (ppm)

#### Lead Based Paint (LBP)

- LBP was assumed to exist on painted surfaces; according to OSHA, any amount of LBP triggers compliance

### Cunniff

#### Asbestos Containing Materials (ACM)

- 108 samples tested, 13 contain asbestos
- ACM in good condition does not present a health issue unless it is disturbed; not necessary to remediate

#### Polychlorinated Biphenyls (PCBs)

- 0 PCBs were found
- Tubes in light fixtures, thermostats, signs and switches were assumed to contain mercury; should be disposed in an EPA approved landfill
- Caulking was assumed to contain PCBs; EPA requires that all be disposed if level exceeds 50 mg/kg (ppm)

#### Lead Based Paint (LBP)

- LBP was assumed to exist on painted surfaces; according to OSHA, any amount of LBP triggers compliance

### Lowell

#### Asbestos Containing Materials (ACM)

- 70 samples tested, 10 contain asbestos
- ACM in good condition does not present a health issue unless it is disturbed by renovation

#### Polychlorinated Biphenyls (PCBs)

- 0 PCBs were found
- Tubes in light fixtures, thermostats, signs and switches were assumed to contain mercury; should be disposed in an EPA approved landfill
- Caulking was assumed to contain PCBs; EPA requires that all be disposed if level exceeds 50 mg/kg (ppm)

#### Lead Based Paint (LBP)

- LBP was assumed to exist on painted surfaces; according to OSHA, any amount of LBP triggers compliance



## Hosmer

### Asbestos Containing Materials (ACM)

Black damproofing on CMU walls at auditorium building	15%
Caulking at pipe stack	5%
Mastic on cork floor under hardwood at library	5%
Particles on slab under hardwood floor at gymnasium	3%
Older adhesive for vinyl baseboard at gymnasium	2%
Glue daub for 1' x 1' acoustical wall tile at classroom 53	2%
Adhesive for 1' x 1' acoustical wall tile at classroom 53	2%
Generator exhaust insulation at basement	30%-50%
Glazing caulking for mesh window over door by room 208	2%
Glazing caulking for mesh window at double door assembly at stairwell by guidance	2%
Glazing caulking for mesh window in wood door at classroom 52	3%
Glue daub for former 1' x 1' acoustical wall tile at nurse heating room	2%
Coating in speaker box at receiving room	5%
9" x 9" Vinyl floor tile at custodian office storage	2%
Mastic for 9" x 9" vinyl floor tile at cust. office storage	5%
Residue black mastic under new vinyl floor tile	2%-3%
Black mastic for 12" x 12" vinyl floor tile at cust. room by classroom 235	3%
Black mastic for white/blue 12" x 12" vinyl floor tile at hallway	3%
Residue black mastic under rubber floor at stairwell	2%
Glue tab on fiberglass insulated duct at mechanical room	10%
Transite pegboard at auditorium lobby custodian closet	10%
Hard joint elbows off fiberglass pipe insulation at hall outside cafeteria from tunnel	5%
Layered paper pipe insulation at physical education office pipe chase	30%
Exterior residue white caulking on concrete at cafeteria window	2%
Exterior door framing caulking at door 17	2%
Exterior horizontal caulking on steel beam over window	2%
Exterior vertical caulking on steel beam over windows at boy's locker	2%

## Cunniff

### Asbestos Containing Materials (ACM)

Mastic/caulking at stack pipe	5%
Glazing caulking for wood entrance door at classroom 24	2%
Interior glazing caulking for metal framed window at stairwell	2%
Interior glazing caulking for metal framed window at hallway	2%
Pipe insulation at first floor girl's room pipe chase	10%
Hard joint insulation at first floor girl's room pipe chase	50%
Mastic for chocolate 12" x 12" vinyl floor tile at basement storage room	5%
Mastic for chocolate 12" x 12" vinyl floor tile at basement storage room	5%
Black glazing caulking for mesh metal door at stairwell	2%
Black glazing caulking for mesh metal door at basement	2%
Exterior old window framing caulking under new caulking	3%
Pipe insulation debris in soil at crawl space	20%
9" x 9" Vinyl floor tile under rubber flooring at stairwell	2%

## Lowell

### Asbestos Containing Materials (ACM)

1927 Roof Core	3%
9" x 9" vinyl floor tile under stairwell rubber flooring	3%
Mastic for 9" x 9" vinyl floor tile under stairwell rubber	5%
Exterior residue caulking behind new window frame caulking	5%
Exterior caulking for boarded up basement window	2%
Exterior caulking for exterior door assembly	2%
Exterior horizontal caulking on lintel over exterior door	2%
Exterior old unit ventilator grille caulking	3%
Exterior grey caulking at red canopy at exterior exit door from west stair	2%
Exterior grey caulking at red canopy at exterior exit door from west stair	2%
<b>No asbestos was found in the 1996 addition</b>	



# Hazardous Materials Investigations: Costs

## Cost Estimates

- The cost includes removal and disposal of all accessible ACM, other hazardous material and an allowance for removal of inaccessible or hidden ACM that may be found during the demolition project.

### Hosmer

#### Z-Shaped Building

Location	Approx. Quantity	Cost
Throughout	Itemized total	\$56,100.00
Library	Floor - 4,000 sf Ceiling - 4,000 sf	\$32,000.00 \$32,000.00
Stage	(1) Curtain	\$4,500.00
Kitchen	(1) Refrigerator	\$4,500.00
Tunnel	Pipe Ins. - 1,500 lf	\$30,000.00
Small Gym	Floor - 5,200 sf	\$35,400.00
Exterior	Caulking/Damp.	\$257,500.00

#### Dining/Gymnasium Wing

Location	Approx. Quantity	Cost
Throughout	Itemized total	\$301,000.00
Various	Floor/Flex. Conn.	\$4,500.00
Large Gym	Floor - 4,000 sf	\$32,000.00
Basement	Exhaust Ins.	\$4,500.00

**Total = \$794,000**

### Cunniff

#### Original Building

Location	Approx. Quantity	Cost
Throughout	(125) Interior Windows/ Doors	\$25,000.00
	(100) Chalkboards	\$20,000.00
	Insulation - Chases	\$5,000.00
	Insulation - Hidden	\$15,000.00
	Misc. - Unknown Tot.	\$25,000.00
Crawl Spaces	Insulation	\$52,500.00
	Soil - 11,000 SF	\$33,000.00
Various	Floor - 500 SF	\$3,000.00

#### Exterior/ Gymnasium

Location	Approx. Quantity	Cost
Exterior	(250) Exterior Windows/ Doors	\$62,500.00
	Roof Caulk - 50 LF	\$1,000.00
	Sewer - Unknown tot.	\$25,000.00
Gymnasium	Floor - 2,800 SF	\$19,600.00

**Total = \$286,600**

### Lowell

#### Original Building

Location	Approx. Quantity	Cost
Throughout	Floor - 7,000 SF	\$28,000.00
	Joint/ Pipe Insul. - 1,000 LF	\$30,000.00
	Misc. - Unknown Tot.	\$15,000.00
Exterior	(112) 1927 Windows	\$28,000.00
	(1) UV Grille	\$300.00
	(7) Doors	\$2,200.00
	Caulking - 50 LF	\$1,500.00
Gymnasium	Floor - Not Tested	\$TBD
Site	Sewer - Unknown tot.	\$25,000

**Total = \$130,000**



## Geotechnical Investigations: Results

### Services Conducted:

- Performed subsurface investigations, with soil samples, to provide foundation design and construction recommendations
- Coordinated and conducted borings at each elementary school site
- Prepared Geotechnical Reports for each elementary school

### Hosmer

#### Recommendations

- The existing fill and natural soil are very silty; Silty soils are very susceptible to disturbance when exposed to moisture - keep dry
- Remove the surficial organic soil, existing fill, and buried organic soil from within the proposed building footprint
- Slab-on-grade bearing on Structural Fill placed directly on top of the natural sand; thickness of the Structural Fill should be at least 12 inches
- Exterior footings and footings in unheated areas should be placed at a minimum depth of 4 feet to provide adequate frost protection
- Wall footings should be designed/constructed with continuous, longitudinal steel reinforcement for greater bending strength
- Total settlement will be about 1 inch and the differential settlement of the footings will be 3/4 inch or less over a distance of 25 feet
- Under-slab drainage system not required

### Cunniff

#### Recommendations

- The existing fill was observed to be variable in composition, density, and with variable amounts of organic matter, per sample.
- The surficial organic soil should be entirely removed from within the proposed building footprint and the proposed parking lots.
- Existing fill presents risks of unpredictable settlement that may result in poor performance of floor slabs and foundations.
- Existing fill should be entirely removed from within the proposed building footprint and replaced with Structural Fill
- Exterior footings and footings in unheated areas should be placed at a minimum depth of 4 feet below the final exterior grade to provide adequate frost protection.
- The proposed floor slab can be constructed as a slab-on-grade, placed directly on natural sand. The thickness of the Structural Fill should be at least 12".
- Under-slab drainage system is needed on the southern third of the proposed building footprint.


### Lowell

#### Recommendations


- The existing fill and natural soil are very silty; Silty soils are very susceptible to disturbance when exposed to moisture - keep dry
- Remove the surficial organic soil, existing fill, and buried organic soil from within the proposed building footprint
- Slab-on-grade bearing on Structural Fill placed directly on top of the natural sand; thickness of the Structural Fill should be at least 12 inches
- Exterior footings and footings in unheated areas should be placed at a minimum depth of 4 feet to provide adequate frost protection
- Wall footings should be designed/constructed with continuous, longitudinal steel reinforcement for greater bending strength
- Total settlement will be about 1 inch and the differential settlement of the footings will be 3/4 inch or less over a distance of 25 feet
- Under-slab drainage system not required




Boring Location Plan  
Hosmer Elem. School




Legend

 Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between October 24 and 25, 2018 and observed by LGCI.

 Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between July 1 and 15, 2019 and observed by LGCI.

Note


Figure based on a drawing titled: "Aerial Mapping Survey, Hosmer Elementary School, Watertown, Massachusetts," prepared by Welch Associates Land Surveyors, Inc. and dated on July 12, 2018, and on a progress drawing titled "Hosmer Plan," dated May 21, 2019 and e-mailed to LGCI by Ai3 Architects LLC on June 3, 2019.

Client: <b>Ai3 Architects LLC</b>	Project: <b>Proposed Hosmer Elementary School</b>	<b>Figure 3 – Boring Location Plan</b>	
 <b>LGCI</b> Lahlaf Geotechnical Consulting, Inc.	Project Location: Watertown, MA	LGCI Project No.: 1849	Date: Aug. 2019



Design Progress

# Geotechnical Investigations: Sample



**Legend**  
 • Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between October 24 and 25, 2018 and observed by LGCI.  
 ◉ Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between July 1 and 15, 2019 and observed by LGCI.

**Note**  
 Figure based on a drawing titled: "Aerial Mapping Survey, Hosmer Elementary School, Watertown, Massachusetts," prepared by Welch Associates Land Surveyors, Inc. and dated on July 12, 2018, and on a progress drawing titled "Hosmer Plan," dated May 21, 2019 and e-mailed to LGCI by Ai3 Architects LLC on June 3, 2019.

Client: <b>Ai3 Architects LLC</b>	Project: <b>Proposed Hosmer Elementary School</b>	<b>Figure 3 - Boring Location Plan</b>	
<b>LGCI</b> Lahlaf Geotechnical Consulting, Inc.	Project Location: <b>Watertown, MA</b>	LGCI Project No.: <b>1849</b>	Date: <b>Aug. 2019</b>


CLIENT: Ai3 Architects LLC	PROJECT NAME: Proposed Hosmer Elementary School
LGCI PROJECT NUMBER: 1849	PROJECT LOCATION: Watertown, Massachusetts
DATE STARTED: 7/10/19	DATE COMPLETED: 7/10/19
BORING LOCATION: Southern side of proposed building	DRILLING SUBCONTRACTOR: Hoffman Environmental Services, Inc.
COORDINATES: NA	DRILLING FOREMAN: Kyle Hoffman
SURFACE EL.: 70 ft. (see note 1)	DRILLING METHOD: Hollow Stem Auger (2-1/4" I.D.)
WEATHER: 80's / Sunny	DRILL RIG TYPE/MODEL: Geoprobe 7822DT
GROUNDWATER LEVELS:	HAMMER TYPE: Automatic
▽ DURING DRILLING: -	HAMMER WEIGHT: 140 lb. HAMMER DROP: 30 in.
▽ AT END OF DRILLING: 12.5 ft. / El. 57.5 ft.	SPLIT SPOON DIA.: 1.375 in. I.D., 2 in. O.D.
▽ OTHER: -	CORE BARREL SIZE: NA
	LOGGED BY: HA CHECKED BY: NP

Depth (ft.)	El. (ft.)	Sample Interval (ft.)	Sample Number	Blow Counts (N Value)	Pen./Rec. (in.)	Remark	Strata	Material Description
0			S1	2-5-27	18/6		Topsoil	S1 - Silty SAND (SM), fine, trace medium, ~25% fines, trace fine gravel, trace organic soil, roots, dark brown, moist (topsoil)
1.5								REMARK 1: Auger chattering from ~1.5' to 3.2', advanced to 4' for next sample.
5	65.0		S2	10-9-9-11 (18)	24/24		Glacial Till	S2 - Silty SAND (SM), fine, trace medium, 25-30% fines, 10-15% fine to coarse subrounded to angular gravel, piece of wood, brown, moist
6			S3	8-10-11-10 (21)	24/24			S3 - Silty SAND (SM), fine, 25-30% fines, 20-25% fine to coarse subrounded gravel, brown, moist
10	60.0		S4	7-13-21-24 (34)	24/20			S4 - Silty SAND with Gravel (SM), fine, 25-30% fines, 25-30% fine to coarse subrounded to angular gravel, brown, moist
15	55.0		S5	24-14-52-65 (66)	24/12			S5 - Silty GRAVEL with Sand (GM), fine to coarse, subangular to angular, 20-25% fines, 15-20% fine to medium sand, gray, wet
20	50.0		S6	19-30-40-56 (70)	24/24			S6 - Sandy SILT with Gravel (ML), slightly plastic, ~25% fine sand, 15-20% fine subrounded gravel, gray, wet
22								Bottom of borehole at 22.0 feet. Backfilled borehole with drill cuttings.
25	45.0							


**GENERAL NOTES:**  
 1. The ground surface elevation was interpolated to the nearest 1/2 foot using drawing titled: "Aerial Mapping Survey, Hosmer Elementary School, Watertown, Massachusetts," prepared by Welch Associates Land Surveyors, Inc. and dated on July 12, 2018.




Boring Location Plan  
Cunniff Elem. School




Legend

 Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI on October 22 and 23, 2018 and observed by LGCI.

 Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between July 7 and 24, 2019 and observed by LGCI

Note


Figure based on a drawing titled: "Aerial Mapping Survey, Cunniff Elementary School, Watertown, Massachusetts," prepared by Welch Associates Land Surveyors, Inc. and dated on April 2, 2018, and dated on April 2, 2018, and on a progress drawing titled "Cunniff Plan," e-mailed to LGCI by Ai3 Architects LLC on June 3, 2019.

Client: <b>Ai3 Architects LLC</b>	Project: <b>Proposed Cunniff Elementary School</b>	<b>Figure 3 –Boring Location Plan</b>	
 <b>LGCI</b> Lahlaf Geotechnical Consulting, Inc.	Project Location: <b>Watertown, MA</b>	LGCI Project No.: <b>1849</b>	Date: <b>Aug. 2019</b>



Design Progress

# Geotechnical Investigations: Sample



**Legend**

- Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI on October 22 and 23, 2018 and observed by LGCI.
- Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between July 7 and 24, 2019 and observed by LGCI.

Note: Figure based on a drawing titled: "Aerial Mapping Survey, Cunniff Elementary School, Watertown, Massachusetts," prepared by Welch Associates Land Surveyors, Inc. and dated on April 2, 2018, and dated on April 2, 2018, and on a progress drawing titled "Cunniff Plan," e-mailed to LGCI by Ai3 Architects LLC on June 3, 2019.

Client: <b>Ai3 Architects LLC</b>	Project: <b>Proposed Cunniff Elementary School</b>	Figure 3 -Boring Location Plan	
<b>LGCI</b> Lahlaf Geotechnical Consulting, Inc.	Project Location: <b>Watertown, MA</b>	LGCI Project No.: <b>1849</b>	Date: <b>Aug. 2019</b>

CLIENT: Ai3 Architects LLC PROJECT NAME: Prop. Cunniff Elementary School  
 LGCI PROJECT NUMBER: 1849 PROJECT LOCATION: Watertown, Massachusetts


DATE STARTED: 7/11/19 DATE COMPLETED: 7/11/19 DRILLING SUBCONTRACTOR: Hoffman Environmental Services, Inc.  
 BORING LOCATION: Southeast corner of proposed building DRILLING FOREMAN: Kyle Hoffman  
 COORDINATES: NA DRILLING METHOD: Hollow Stem Auger (2-1/4" I.D.)  
 SURFACE EI.: 112.5 ft. (see note 1) TOTAL DEPTH: 15 ft. DRILL RIG TYPE/MODEL: Geoprobe 7822DT  
 WEATHER: 80's / Cloudy HAMMER TYPE: Automatic  
 GROUNDWATER LEVELS: HAMMER WEIGHT: 140 lb. HAMMER DROP: 30 in.  
 DURING DRILLING: 6.0 ft. / El. 106.5 ft. Based on soil samples. SPLIT SPOON DIA.: 1.375 in. I.D., 2 in. O.D.  
 AT END OF DRILLING: - CORE BARREL SIZE: NA  
 OTHER: - LOGGED BY: HA CHECKED BY: NP

Depth (ft.)	EI. (ft.)	Sample Interval (ft.)	Sample Number	Blow Counts (N Value)	Pen./Rec. (in.)	Remark	Strata	Material Description
0	112.3						Topsoil	S1 - Top 3": Silty SAND (SM), fine, trace medium, ~25% fines, trace fine gravel, trace organic fines, roots, dark brown, moist (topsoil)
2	110.0		S1	3-3-3-3 (6)	24/8		Subsoil	Bot. 5": Silty SAND (SM), fine to medium, trace coarse, 20-25% organic fines, roots, brown, moist
4			S2	5-13-13-27 (26)	24/5			S2 - Silty SAND with Gravel (SM), fine to coarse, 35-40% fines, 20% fine subrounded gravel, brown, moist
6			S3	12-13-22-14 (35)	24/15			S3 - Silty SAND with Gravel (SM), fine to coarse, 20-25% fines, ~15% coarse subrounded to angular gravel, brown, moist
8	105.0		S4	24-30-20-16 (50)	24/2		Glacial Till	S4 - Silty SAND (SM), fine, trace medium, 20-25% fines, 10-15% fine to coarse subrounded gravel, brown, wet
10			S5	7-23-27-45 (50)	24/24			S5 - Silty SAND (SM), fine, trace medium, 20-25% fines, ~5% fine subrounded gravel, brown, wet
12	100.0		S6	23-19-27-49 (46)	24/24	1		REMARK 1: Auger chattering at ~13'. S6 - Similar to S5
15								Bottom of borehole at 15.0 feet. Backfilled borehole with drill cuttings.
20	95.0							
25	90.0							


**GENERAL NOTES:**  
 1. The ground surface elevation was interpolated to the nearest 1/2 foot based on a drawing titled: "Aerial Mapping Survey, Cunniff Elementary School, Watertown, Massachusetts," prepared by Welch Associates Land Surveyors, Inc. and dated on April 2, 2018.




Boring Location Plan  
Lowell Elem. School




Legend

 Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between October 26 and 29, 2018 and observed by LGCI.

 Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between July 8 and 15, 2019 and observed by LGCI.

Note


Figure based on and on a progress drawing titled "Lowell Plan," dated May 21, 2019 and e-mailed to LGCI by Ai3 Architects LLC on June 3, 2019.

Client: <b>Ai3 Architects LLC</b>	Project: <b>Proposed Lowell Elementary School</b>	<b>Figure 3 – Boring Location Plan</b>	
 <b>LGCI</b> Lahlaf Geotechnical Consulting, Inc.	Project Location: Watertown, MA	LGCI Project No.: 1849	Date: Aug. 2019



Design Progress

# Geotechnical Investigations: Sample



**Legend**  
 ○ Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between October 26 and 29, 2018 and observed by LGCI.  
 ⊕ Approximate location of borings advanced by Hoffman Environmental Services, Inc. of North Kingstown, RI between July 8 and 15, 2019 and observed by LGCI.

**Note**  
 Figure based on and on a progress drawing titled "Lowell Plan," dated May 21, 2019 and e-mailed to LGCI by Ai3 Architects LLC on June 3, 2019.

Client: <b>Ai3 Architects LLC</b>	Project: <b>Proposed Lowell Elementary School</b>	<b>Figure 3 – Boring Location Plan</b>	
<b>LGCI</b> Lahiaf Geotechnical Consulting, Inc.	Project Location: <b>Watertown, MA</b>	LGCI Project No.: <b>1849</b>	Date: <b>Aug. 2019</b>

<b>CLIENT:</b> Ai3 Architects LLC	<b>PROJECT NAME:</b> Prop. Lowell Elementary School
<b>LGCI PROJECT NUMBER:</b> 1849	<b>PROJECT LOCATION:</b> Watertown, Massachusetts
<b>DATE STARTED:</b> 7/12/19	<b>DATE COMPLETED:</b> 7/12/19
<b>BORING LOCATION:</b> Southeast corner of proposed building footprint	<b>DRILLING SUBCONTRACTOR:</b> Hoffman Environmental Services, Inc.
<b>COORDINATES:</b> NA	<b>DRILLING FOREMAN:</b> Kyle Hoffman
<b>SURFACE EI.:</b> 85.5 ft. (see note 1)	<b>TOTAL DEPTH:</b> 10.3 ft.
<b>WEATHER:</b>	<b>DRILL RIG TYPE/MODEL:</b> Geoprobe 7822DT
<b>GROUNDWATER LEVELS:</b>	<b>HAMMER TYPE:</b> Automatic
▽ <b>DURING DRILLING:</b> -	<b>HAMMER WEIGHT:</b> 140 lb. <b>HAMMER DROP:</b> 30 in.
▽ <b>AT END OF DRILLING:</b> N/E	<b>SPLIT SPOON DIA.:</b> 1.375 in. I.D., 2 in. O.D.
▽ <b>OTHER:</b> -	<b>CORE BARREL SIZE:</b> NA
	<b>LOGGED BY:</b> JV / HA <b>CHECKED BY:</b> NP

Depth (ft.)	EI. (ft.)	Sample Interval (ft.)	Sample Number	Blow Counts (N Value)	Pen./Rec. (in.)	Remark	Strata	Material Description
85.0		0.5	S1	7-6-5	18/11		Asphalt	S1 - Top 7": Poorly Graded GRAVEL with Silt (GP-GM), fine, trace coarse, subrounded to angular, 10-15% fines, 35-40% fine to coarse sand, asphalt, brown, moist
		2	S2	7-4-5-4 (9)	24/5		Fill	Bot. 4": Silty SAND with Gravel (SM-SW), fine to coarse, 15-20% subrounded to angular gravel, brown, moist
		4	S3	3-2-2-12 (4)	24/3			S2 - Silty GRAVEL with Sand (GM), medium to coarse, 20-25% fines, 15-20% subrounded to angular gravel, brown, moist
		5	S4	39-74-100/5"	17/17			S3 - Silty SAND with Gravel (SM), fine to medium, trace coarse, 20-25% fines, 15-20% subrounded to angular gravel, brown, moist
80.0		6					Weathered Rock	S4 - Silty GRAVEL with Sand (GM), fine to coarse, 25-30% fines, 20-25% fine to coarse sand, light gray, moist (possible weathered rock)
		7.4						
75.0		10.3	S5	100/3"	3/3			S5 - Silty SAND with Gravel (SM), fine to medium, trace coarse, 25-30% subrounded to angular gravel, light gray, moist (possible weathered rock)
								Bottom of borehole at 10.3 feet. Backfilled borehole with drill cuttings.

**GENERAL NOTES:**  
 1. The ground surface elevation was interpolated to the nearest 1/2 foot based on drawing C1 titled: "Grading Plan, Lowell Elementary School, 175 Orchard Street, Watertown, Massachusetts," prepared by The Vertex Companies, Inc. dated on July 5, 2019 and provided to LGCI by Ai3 Architects LLC via email on July 8, 2019.



Questions?  
**Thank you**

